

CIVIL WORK					
S.No.	Description of Work	Qty.	Unit	Rate	Amount
14	Cement concrete work in beams, suspended floors, roofs having slope upto 15 deg, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral staircases above plinth level upto floor five level excluding the cost of centring, shuttering, finishing and cement concrete 1:1.5:3(1cement : 1.5coarse sand : 3 graded Quartzite stone aggregate 10mm nominal size) \Including add the water proof treatment chemical i.e Conplast X421IC and recron polyster fibre 35 as per manufacture specifications to complete the job as per Instructions of Engineer In-Charge	1.15	cum		
15	Providing and fixing of Shabad stone with 20mm to 25mm thick for chajjas with cement mortar 1:4 to arrange nesserary requirement like scaffolding to complet the job as per instructions of Engineer In-Charge (Single stone if required length	9.00	Sqm		
16	Providing and fixing of one side polished Shabad stone with 20mm to 25mm thick , each tile bind with 5 layers for Lintels (for door & windows 0.3m width x 1.6m length) with cement mortar 1:4 to arrange nesserary requirement like scaffolding and binding with each tile copper wire 1mm dia 10 rounds at every 400mm centre to centre for the length of lintel to complet the job as per instructions of Engineer-In-Charge	7.00	Each		
17	Providing wood work in wooden beams in roofs including making good the holes in walls and painting with oil type wood preservative of approved brand and manufacture complete including necessary ss screws, julas etc and removal of rubbish to the dumping ground within campus as per instructions of Engineer-In-Charge				
	Not exceeding 4.00 metres in length.	0.63	cum		

Signature of Contractor with Stamp